

ADDENDUM TO THE TENDER NO. HBL/TEN/PUB/20-21/225 DATED 06.02.2021 FOR SUGUALI - ETHANOL PLANT		
TENDER		
Sr. No.	Particulars	Remark
1	Sludge Decanter unit - 15 m3 X 3 No's	Excluded from the scope of supply
2	<b>Wash Settling Conical tank</b>	Included in the scope of supply with the related piping & Valves
	Type - Conical Bottom	
	Capacity - 180 m3 (Working)	
	MOC - SS 304	
3	<b>Sludge Transfet Pump</b>	Included in the scope of supply with the related piping & Valves
	Type - Screw	
	Capacity - 6 m3/hr	
	Qty - 1 + 1	
	MOC - Internal SS	
4	<b>Sludge Trough Tank with Agitator</b>	Existing to be used. Necessary changes if any to be done by supplier.
	Type - Cylindrical	
	Capacity - 1 m3	
	MOC - SS 304	
5	<b>Spent Wash Digester</b>	The existing Bio-Digester shall be used for raw spent wash evaporation condensate treatment. The necessary corrections/changes with epoxy painting for required gas zone to be done by supplier. Sugauli unit Digester roof leakages to be rectified by supplier.
	Type - Cylindrical with top dom	
	Capacity - Suitable for existing 60 KLPD spent wash treatment	
	Qty - 1 No	
	MOC - MS	
6	Degasser Tower, Lamella Clarified, Pumps, Motors, Gas Holde, Flare Stake etc.	Existing to be used with necessary overhauling
7	<b>CPU - Anaerobic Hybrid Digester</b>	Existing CPU anaerobic hybrid digester with packing media to be converted in Aeration tank with required diffusers and piping circuites. The converted Aeration tank shall be use for further treatment of evaporation condensate after Bio-Digester outlet. The required equipments, piping & valves, blower upgradation, support etc. shall be in supplier scope.
	Type - Reactangular with top open	
	Capacity - 740 m3	
	Qty - 1 No	
	MOC - Civil	

**NOTE :** All other technical specifications, commercial terms & conditions remains same as per the tender NO. HBL/TEN/PUB/20-21/225 DATED 06.02.2021 FOR SUGUALI